

**Embassy of India**  
**Kathmandu**  
**TENDER NOTICE**

Sealed tender documents/quotations are invited directly from reputed and experienced bidders for **replacement of worn out kitchen cup boards with new modular kitchen shelves, cabinets and drawers etc, in India House within Embassy premises**. The last date of receipt of offer in sealed envelope is on or before – 03 July 2017 up to 1700 hrs. Entire details of scope of work for tender documents are available on website [www.indianembassy.org.np](http://www.indianembassy.org.np) and [www.eprocure.gov.in](http://www.eprocure.gov.in). These documents can also be collected from **Attaché (Admin), Attaché (Establishment)** Tel 01-4411851 Ext. 4238/.

**Kat/Adm/872/5/2011**

Sd/-  
**(Head of Chancery)**

## Scope of work

**Name of work: Replacement of worn out kitchen cup boards with new modular kitchen shelves, cabinets, and drawers etc, in India House within Embassy Premises.**

Item	Abstract of Cost-Description	Quantity	Rate	Unit
	<b>Name of Work: Replacement of kitchen cup boards with modular kitchen cup boards in Ground floor located within India House</b>			
<b>1</b>	<b>Dismantling wooden boarding's in lining of walls and partition, excluding supporting members but including stacking within 50 meter lead:</b>			
<b>1.1</b>	<b>Thickness above 25 mm up to 40 mm</b>	<b>107</b>		<b>sqm</b>
<b>2</b>	<b>Dismantling stone slab flooring laid in cement mortar including stacking of servable material and disposal of unserviceable material within 50 meter lead</b>	<b>15</b>		<b>sqm</b>
<b>3</b>	<b>Taking out kitchen sink with drain board from kitchen top slab of various sizes including stacking of useful materials near the site disposal of unserviceable material within 50 meters lead</b>	<b>5</b>		<b>Each</b>
<b>4.1</b>	<b>Providing and laying ceramic glazed floor tiles of size 300x300 mm of first quality conforming to IS: 15622, of approved make, in all colors, such as white, Ivory, grey, Fume red brown laid on 20 mm thick cement mortar 1:4 (1 cement:4 coarse sand) including pointing the joints with white cement and matching pigment etc. complete</b>	<b>9</b>		<b>sqm</b>
<b>4.2</b>	<b>Providing and fixing first quality ceramic glazed wall tiles conforming to IS: 15622 of approved make in all colors, shades except burgundy, bottle green, black of any size as approved by Engineer-in-charge in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement:3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm including pointing in white cement mixed with pigment of matching shade complete</b>	<b>20</b>		<b>sqm</b>

5	Providing and fixing 16 to 18 mm thick mirror polished pre-molded and pre-polished machine cut for kitchen platforms, vanity counters, window sills, fascias and similar locations of required size, approved shade, color and texture including rubbing, molding and polishing edges to give high gloss finish etc, complete at all levels			
5.1	Green marble/ black marble/			
5.1.1	Area of slab over 0.50 sqm	5		sqm
5.2	Granite of any color and shade			
5.2.1	Area of slab over 0.50 sqm	10		sqm
6	Providing and fixing Stainless steel magic corner (Left/ Right) in kitchen of width 910 and depth 490 and height 540 mm as per manufacturers specification	1		Each
7	Providing and fixing stainless steel A ISI (18x8) kitchen sink as per IS:13983 with CI brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required:			
7.1	Kitchen Sink with drain board			
7.1.1	510x1040 mm 2-bowl depth 250mm	1		Each
7.2	Kitchen sink without drain board			
7.2.1	610 x 460 mm bowl depth 200 mm	3		Each
8	Providing and fixing CP brass angle valve for basin mixer and geyser points of approved quality conforming to IS: 8931 a) 15 mm nominal bore			
8.1	15 mm nominal bore (Jaguar or equivalent)	10		Each
9	Providing and fixing kitchen sink mixer (single lever) of Jaguar or equivalent			
9.1	15 mm nominal bore	5		Each
10	Making connection of GI distribution branch with GI main of following by providing and fixing tee, including cutting and threading the pipe etc, complete :			
10.1	25 to 40 mm nominal bore	10		Each
11	Providing and fixing PVC waste pipe for sink or wash basin including CP waste fittings complete			
11.1	Flexible pipe with cp coupling			
11.1.1	32 mm dia	5		Each

12	Providing and applying white cement based putty of average thickness 1 mm of approved brand and manufacture over the plastered wall surface to prepare the surface even and smooth	40		sqm
13	Providing and fixing 16 mm thick teak veneer plywood (seasoned wood- hot pressed) for kitchen shutters including kitchen racks with all locking arrangements etc. complete as directed by the Engineer-in-charge	34		sqm
14	providing and fixing decorative high pressure laminated sheet of plain wood grain in gloss/matt/suede finish with hi-density protective surface layer and reverse side of adhesive bonding quality conforming to IS: 2046 type S, including cost of ahesive of approve quality			
14.1	1 mm thick	68		sqm
15	Providing and fixing modular kitchen with 16 mm thick teak veneer plywood ( seasoned wood- hot pressed wood) including all shutters, shelves, cabinets etc., with 1 mm thick mica sheet all over surface areas, all fittings, hinges, handles, locking arrangements, magnet, drawers etc. complete as directed by the Engineer-in-charge (Payment will be made as per front shutter area) as per manufactures specification	135		sq ft
16	French sprit polishing			
16.1	Two or more coats on new work including a coat of wood filler	50		sqm
17	Providing and fixing kitchen chimney with in-door and out -door units, front toughened glass, LED lights, motor with top, made in Italy or equivalent of Airflow 1250 cubic meter per hour	1		Each
18	Providing and fixing LED lighting arrangements in modular kitchen area as directed by the Engineer-in-Charge	6		Each

**Embassy of India  
Kathmandu**

**Additional conditions:**

**Sub: Replacement of worn out kitchen cup boards with new modular kitchen shelves, cabinets, drawers etc. in India House within Embassy premises**

1. The work shall be completed within 30 days (Thirty days) from the date of award of the work.
2. 3% Penalty will be recovered from the bill for delay in every 30 days.
3. Only best quality and approved materials should be used for the proposed Work
4. The work shall be carried out strictly as per the latest CPWD specifications along with the updated correction slips issued by the CPWD from time to time.
5. Agency should take care for covering the wooden floors and wooden walls with plastic sheets.
6. The rate includes at all floors and all heights. Nothing shall be paid extra.

**The Head of Chancery**